



तिनाउ गाउँपालिका

Tinau Rural Municipality

गाउँ कार्यपालिकाको कार्यालय

Office Of The Rural Municipal Executive

पत्र सख्या /Letter No.:

चलानी नं. /Ref. No.:

दोभान, पाल्पा
Dobhan, Palpa
स्था २०७३/ Estd. 2017 A.D.
तिनाउ गाउँपालिका
लुम्बिनी प्रदेश, नेपाल
२०७३

लुम्बिनी प्रदेश, नेपाल
Lumbini Province, Nepal

दररेट पेश गर्ने सम्बन्धी सूचना

प्रथम पटक प्रकाशित मिति २०८२।१२।२७


१. तिनाउ गाउँपालिकाद्वारा विभिन्न निर्माण व्यवसायी संग तपशिल बमोजिमको कार्य गर्न दररेट पेश गर्नका लागि यो सूचना प्रकाशित गरिएको छ ।

तपशिल

क्र. स.	कार्य विवरण	जम्मा रकम (मुल्य अभिवृद्धि कर ,भ्याट सहित) कन्टेन्जेन्सी वाहेक	दररेट पेश गर्ने अन्तिम मिति	कै.
१	खानेपानी मर्मत सम्भार तथा निर्माण गर्ने कार्य तिनाउ-०३ (आदर्श आ वि टंकी निर्माण तथा पार्टेशन,देउराली खानेपानी, झुम्सा खानेपानी, पैठेडाँडा बाटो मर्मत ,जस्तापाता खरीद)	६,६७,७५५.७१	२०८३।०९।०३	

२. दररेट पेश गर्ने निर्माण व्यवसायीले अनिवार्य रूपमा दररेट पेश गर्ने व्यहोरा सम्बन्धमा लिखित निवेदन सहित नविकरण भएको फर्म/ कम्पनी दर्ता प्रमाणपत्रको प्रतिलिपी, नविकरण भएको व्यवसाय दर्ता (निर्माण व्यवसायी इजाजत प्रमाण पत्र) प्रमाणपत्रको प्रतिलिपी, मु.अ.क.दर्ता प्रमाणपत्रको प्रतिलिपी र आर्थिक वर्ष २०८१/८२ को करचुक्ता प्रमाणपत्रको प्रतिलिपी संलग्न गरि पेश गर्नुपर्नेछ ।

३. BOQ, Specification यस कार्यालयको Website बाट समेत डाउनलोड गर्न सकिनेछ ।


दिनेश प्रशासकीय अधिकृत
प्रमुख प्रशासकीय अधिकृत



तिनाउ गाउँपालिका
गाउँकार्यपालिकाको कार्यालय

स.ने.प.कार्य नं. ५०१

सोमान पाल्पा सुम्बिनी प्रदेश नेपाल
कार्यालय कोड नं.: ८०१०५५५०३
निर्माण/कार्यको परिमाण अनुमान फारम

सोमान पाल्पा
सुम्बिनी प्रदेश, नेपाल
२०७३

प्रमुख प्रशासकीय अधिकृत

कार्यक्रम/योजनाको नाम मर्मत सम्भार र खानेपानी तथा सरसफाई आयोजना
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल तिनौटा गाउँपालिका वडा नं. ३ को विभिन्न स्थानमा
सम्पन्न हुने अनुमानित अवधि-तीन महिना

आर्थिक वर्ष २०८२-८३
बजेट उप शीर्षक नं.

Sno.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)	Remarks
A	पेढे डाँडा गोरेटो बाटो मर्मत						
1	Providing and laying of Plain Cement Concrete (Using River Sand And OPC) PCC Grade M 15 (or 1 2 4 for nominal mix) including formwork as complete as per Drawing and Technical Specifications	Cum	5 54				
B	आदर्श आ.वि. पाठशाला						
1	BRICK WORK Providing and laying, brick work in 1 4CM in foundation and superstructure with approved quality first class brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete in all types and thickness of walls, associated cornices, columns, etc. as per drawings, specification and instruction of engineer, all complete.	Cum	2 48				
2	P.C.C. FOR R.C.C. Providing and laying in position machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete work using OPC cement with various design mixes (various grades of concrete) with 20 mm graded machine crushed stone aggregate of approved quality in various locations and heights including transportation of concrete to site of placing, compaction, finished to required line and level, protection and curing, etc. all complete as per drawings, specifications and the instructions of the Engineer, but excluding the cost of centring, shuttering, and reinforcement, but including the cost of admixtures in recommended proportions (as per IS 9103) to accelerate, retard setting of concrete improve workability, improve strength without impairing strength and durability as per direction of Engineer for the following grades of the structural concrete (Mix design is essential) a) P.C.C. of M20 (1 1 5 3)	Cum	0 18				
3	STEEL REINFORCEMENT Providing and fixing in position Fe 500 steel reinforcement of various diameter conforming to relevant IS code in R.C.C. works including straightening, cutting, bending, binding with 20 SWG annealed wire for tying the reinforcement bars at each junctions (binding wire shall not be measured separately) including all waste and cut pieces, provision for adequate numbers of spacers, chairs, providing and placing cement mortar (1:1) cover blocks to keep the bars in intended position at all levels all complete as per drawings, specifications and instructions of the Engineer. (Authorized lap length and for the bar length exceeding 10 meter in length shall be measured for the payment)	Kg	15 77				

Prepared By

Checked By

Approved By



तिनाउ गाउँपालिका

म.ले.प.फारम नं. ५०१

गाउँकार्यपालिकाको कार्यालय

द्रोभान पाल्पा लुम्बिनी प्रदेश नेपाल

कार्यालय कोड नं.: ८०१०५५५०३

लिमिण कार्यको परिमाण अनुमान फारम

द्रोभान पाल्पा
लुम्बिनी प्रदेश, नेपाल
२०७३

प्रमुख प्रशासकीय अधिकारी

कार्यक्रम/योजनाको नाम: मर्मत सम्भार र खानेपानी तथा सरसफाई आयोजना
कार्यक्रम / योजनाको नाम र कार्यन्वयन हुने स्थल: तिनाउ गाउँपालिका वडा नं. ३ को विभिन्न स्थानमा
सम्पन्न हुने अनुमानित ब्रबधि-तीन महिना

वार्धिक वर्ष २०८२-८३
बजेट उप शीर्षक नं.

Sno.	Item Description	Unit	Quantity	Bidder's Rate (NPR).	Bidder's Rate (in words)	Total Amount (NPR)	Remarks
4	FORMWORK Supplying and laying centering, shuttering of various pattern formworks with 19/12 mm thick water proof ply wood & steel adjustable props for all kinds of RCC works for foundations, columns, shear walls, beams, slab, staircase, lintel, sill, pergola, including nails, propping scaffolding, staging, supporting and bracing in proper lines and level, sealing the joints with heavy duty brown self adhesive tape, aligning to line and levels including Ties, PVC Spacer, Providing openings/ cutouts/ pockets, applying deshuttering chemical, deshuttering as approved by the Engineer etc., complete at all levels as per drawing, specifications and instructions of the Engineer	Sqm	1 60				
5	CEMENT SAND PLASTER Providing and laying, cement sand plastering on floor, wall, ceiling, skirting, dado, cornices, etc. of good finish, including raking the joints, cleaning and wetting the surface and curing the works all complete, as per drawing, specification and instruction of engineer, all complete a) 20mm thick plaster in 1:5 mix	Sqm	43 20				
6	DISTEMPER PAINTING Providing and applying, inside painting work on wall and ceiling of approved color including necessary primer (as per product manual) to give uniform color after rendering surface clean and moist (where necessary) as per specifications, drawings, and instruction of the engineer, all complete	Sqm	129 60				
C	Procurement Supply and Delivery of CGI Sheet						
1	Procurement Supply and Delivery of Nepal Standard Colour 26 Gauge Medium (0.35mm) CGI sheet	Bundle	16 00				
D	आदर्श, आ वि ज्यामिरे खानेपानी व्यवस्थापन						
1	Site clearance including cutting the shrub, grass, bushes, tree if required etc. & uprooting, dressing, levelling & disposing the materials 30 m from the site as specified complete work as per specification and instruction of site engineer	Sqm	16 00				
2	Earth work in excavation in hard, boulder mixed soil for foundation trench including Timbering and pumping out water from the trenches(if necessary), Ramming of bottom, lift up to 2m lead 10m, stacking of excavated materials, clear from the edge of foundation trench with all complete as per specification & instruction of site engineer	Cum	1 87				
3	STONE/BOULDER SOLING Providing and laying boulder/stone soling in foundation of water tank, floor, with approved quality stone/boulder in required line and leveling all complete as per drawings, specifications and instructions of the Site Incharge	Cum	1 15				

Prepared By:

Checked By:

Approved By:



विनाज गाउँपालिका
गाउँ कार्यपालिकाको कार्यालय
चौमले पाट्या चुम्बिनी प्रवेश नेपाल
कार्यालय फोन नं. ८०१०२२२०३
विनाज कार्यको परिमाण अनुमान फारम

प्र.ने.प्र.फारम नं. २०१

[Handwritten Signature]
मुख्य कार्यपालिका अधिकारी

कार्यक्रम/योजनाको नाम, शर्तित सम्भार र खानेपानी तथा सरसफाई आयोजना
कार्यक्रम / योजनाको नाम र कार्यान्वयन हुने स्थल: विनाज गाउँपालिका वडा नं. ३ को विभिन्न स्थानमा
सम्पन्न हुने अनुमानित अवधि: तीन महिना

सर्बिक नं. २०८१/०३
पत्र नं. ३१/०३१८३

Sno.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)	Remarks
1	देउराली खानेपानी ब्यबस्थापन						
1	Site clearance including cutting the shrub, grass, bushes, tree if required etc. & uprooting, dressing, levelling & disposing the materials 30 m from the site as specified complete work as per specification and instruction of site engineer	Sqm	4.00				
2	Earth work in excavation in hard boulder mixed soil for foundation trench including Timbering and pumping out water from the trenches(if necessary). Ramming of bottom lift up to 2m lead 10m, stacking of excavated materials, clear from the edge of foundation trench with all complete as per specification & instruction of site engineer	Cum	0.51				
3	STONE/BOULDER SOLING Providing and laying boulder/stone soling in foundation of water tank, floor, with approved quality stone boulder in required line and leveling all complete as per drawings, specifications and instructions of the Site Incharge	Cum	0.34				
4	Manually mixed Plain cement Concrete (PCC) for RCC works (1:1.5:3) M20 for structural work with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer	Cum	1.21				
5	Formwork, shuttering, centering for Vertical Wall with 19 mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization all complete	Sqm	12.00				
6	STEEL REINFORCEMENT Providing and fixing in position Fe 500 steel reinforcement of various diameter conforming to relevant IS code in R C C works including straightening, cutting, bending, binding with 20 SWG annealed wire for tying the reinforcement bars at each junctions (binding wire shall not be measured separately) including all waste and cut pieces, provision for adequate numbers of spacers, chairs, providing and placing all complete as per drawings, specifications and instructions of the Engineer. (Authorized lap length and for the bar length exceeding 10 meter in length shall be measured for the payment)	Kg.	123.82				
7	CEMENT SAND PLASTER 12.5 MM THICK Providing and laying, 12.5mm thick plaster in 1:4 mix on water tank, wall etc. of good finish, including raking the joints, cleaning and wetting the surface and curing the works all complete, as per drawing, specification and instruction of engineer, all complete	Sqm	12.04				
8	3 mm thick cement sand (1:1) punning on floor, water tank etc. including mixing laying and rubbing with steel trowel to a hard, smooth and shining surface and curing all complete	Sqm	5.80				
9	Standard Manhole cover set 60x60 cm size	Set	1.00				
10	32 mm GI Pipe- Medium Class	rm	0.60				
11	32 mm Nipple 10 CM Long	nos	2.00				
12	32 mm Gate Valve	nos	1.00				
13	50 mm GI Pipe Medium class	rm	1.20				
14	32 mm GI Union	nos	3.00				
15	50 mm End cap	nos	1.00				

Prepared By

Checked By

Approved By



तिनाउ गाउँपालिका
गाउँकार्यपालिकाको कार्यालय

सं.सं.प.कार्यालय नं. २०१

सोमान पाण्डे लुम्बिनी प्रदेश नेपाल
क्रमांक नं. ८०१०२५०३
निर्माण कार्यको परिमाण अनुमान फारम

सोमान, पाण्डे
लुम्बिनी प्रदेश, नेपाल
२०७३

वार्डिक वर्ष २०८२-८३
नबेट उप वार्डिक नं.

Green
प्रमुख प्रशासकीय अधिकृत

कार्यक्रम/सोझनाको नाम: मर्मत सम्भार र खानेपानी तथा सरसफाई आयोजना
कार्यक्रम / सोझनाको नाम र कार्यान्वयन हुने स्थल: तिनाउ गाउँपालिका वडा नं. ३ को विभिन्न स्थानमा
सम्पन्न हुने अनुमानित अवधि: तीन महिना

Sno.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)	Remarks
F	जुम्सा बजार खानेपानी ब्यबस्थापन						
1	Earth work in excavation in hard ,boulder mixed soil for foundation trench including Timbering and pumping out water from the trenches(if necessary), Ramming of bottom.lift up to 2m lead 10m, stacking of excavated materials , clear from the edge of foundation trench with all complete as per specification & instruction of site engineer	Cum	0.11				
2	STONE/BOULDER SOLING: Providing and laying boulder/stone soling in foundation of water tank, floor, with approved quality stone/boulder in required line and leveling all complete as per drawings, specifications and instructions of the Site Incharge	Cum	0.03				
3	Manually mixed Plain cement Concrete (PCC) for RCC works (1:2:4) M15 for Super structural work with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	Cum	0.096				
4	Formwork, shuttering, centering for Vertical Wall with 19 mm thick waterproof ply board and steel post for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization all complete.	Sqm.	19.20				
5	40 mm GI Pipe- Medium Class	RM	100.00				
6	40 mm GI Union	Nos	19.00				
Total Cost for all Item							
VAT @ 13 %							
Grand Total							
<p>The total price of our Bid, excluding any discounts offered is :</p> <p>Name of Bidder/Suppliers</p> <p>Address</p> <p>Bidder's /Suppliers Legal Name</p> <p>Bidder's /Suppliers Address:</p> <p>Bidder/Suppliers Country of Registration:</p> <p>Bidder/Suppliers Year of Registration:</p> <p>Bidder/Suppliers Authorized Representative Information: Name:</p> <p>Address: Telephone/Fax numbers:</p> <p>Email Address</p>							